

Datasheet T13

Mass Flow Meters for Gases

> Introduction

Bronkhorst High-Tech model T13 Mass Flow Meters (MFM) are suited for precise measurement of virtually all conventional process gases, even if these contain particulates or traces of moisture. The in-line MFM consists of a thermal mass flow sensor and a microprocessor based pc-board with signal and fieldbus conversion and a PID controller for optional mass flow control by means of a separately mounted control valve. The IN-FLOW^{CTA} model is of rugged design (IP65) for use in industrial environments or even Zone 2 hazardous areas, with optional ATEX Cat. 3 approval. The mass flow, expressed in normal liters per minute or per hour by default, is provided as analog signal or digitally via RS232 or fieldbus. The flow range and wetted materials are determined depending of the type of gas and the process conditions of the application.



> Technical specifications

Measurement / control system

Accuracy (incl. linearity) (based on actual calibration)	: $\pm 1\%$ Rd plus $\pm 1\%$ FS
Repeatability	: < 0,2% FS typical
Turndown table)	: 1 : 50 or 1 : 100 (see flow range Operating pressure
Operating pressure	: 0...10 bar(g)
Pressure sensitivity	: 0,3% Rd/bar typical at Air
Operating temperature sensitivity	: 0...50 °C Temperature : zero: < $\pm 0,1\%$ FS/°C; span: < $\pm 0,2\%$ Rd/°C
Leak integrity (outboard)	: $< 2 \times 10^{-9}$ mbar l/s He
Altitude sensitivity	: max. error at 90° off horizontal 0,2% at 1 bar, typical N ₂
Response time (sensor t _{63%})	: 0,9 sec
Warm-up time	: 30 min. for optimum accuracy 2 min. for accuracy $\pm 2\%$ FS

Mechanical parts

Material (wetted parts)	: SS316; other on request
Process connections	: standard: none;
Seals	: standard: Viton®; options: EPDM, FFKM (Kalrez®)
Ingress protection (housing)	: IP65

Although all specifications in this datasheet are believed to be accurate, the right is reserved to make changes without notice or obligation.

IN-FLOW^{CTA} Mass Flow Meter model T13

Electrical properties

Power supply	: +15...24 Vdc
Power consumption	: max. 125 mA; add 50 mA for PROFIBUS, if applicable
Analog output	: 0...5 (10) Vdc or 0 (4)...20 mA (sourcing output)
Digital communication	: standard RS232; options: PROFIBUS-DP®, DeviceNet™, Modbus-RTU, FLOW-BUS

Electrical Connections

Analog/RS232	: 8-pin DIN male
PROFIBUS-DP®	: bus: 5-pin DIN male; power: 8-DIN male
DeviceNet™	: 5-pin M12 male
Modbus-RTU/FLOW-BUS	: 5-pin M12 male

> Ranges (based on Air)

Model	minimum	maximum
T13	0,4...20 l _n /min	2...200 l _n /min
<i>Intermediate ranges are available</i>		

По вопросам продаж и поддержки обращайтесь:


Волгоград +7 (8442) 45-94-42
Екатеринбург +7 (343) 302-14-75
Ижевск +7 (3412) 20-90-75
Казань +7 (843) 207-19-05

Краснодар +7 (861) 238-86-59
Красноярск +7 (391) 989-82-67
Москва +7 (499) 404-24-72
Ниж.Новгород +7 (831) 200-34-65

Новосибирск +7 (383) 235-95-48
Омск +7 (381) 299-16-70
Пермь +7 (342) 233-81-65
Ростов-на-Дону +7 (863) 309-14-65


Самара +7 (846) 219-28-25
Санкт-Петербург +7 (812) 660-57-09
Саратов +7 (845) 239-86-35
Сочи +7 (862) 279-22-65

> Model number identification



> Thermal mass flow measuring principle


IN-FLOW^{CTA} Mass Flow Meters with inline sensor (no by-pass) consist of a straight flow channel, into which two stainless steel probes protrude; a heater probe and a temperature sensor probe. A constant temperature (ΔT) is created between the two probes and the energy required to maintain this ΔT is proportional to the mass flow rate. Based on this concept, mass flow can be measured with low pressure drop, mainly caused by the gas fittings and the mesh screens which are incorporated for flow conditioning (see figure below). Compared to traditional thermal MFMs and MFCs with by-pass, the construction of the direct measuring CTA principle (Constant Temperature Anemometry) is less sensitive to humidity and contamination.



Functional scheme of the thermal mass flow sensor


> State of the art digital design

Todays IN-FLOW^{CTA} series are equipped with a digital pc-board, offering high accuracy, excellent temperature stability and fast response. The basic digital pc-board contains all of the general functions needed for measurement and control. In addition to the standard RS232 output the instruments also offer analog I/O. Furthermore, an integrated interface board provides DeviceNet™, PROFIBUS-DP®, Modbus-RTU or FLOW-BUS protocols.




Functional scheme of the digital PC-board


> Hook-up diagram for analog or RS232 communication



> Hook-up diagrams for fieldbus communication



> Dimensions (mm) and weight (kg)




Dimension table adapters (RS-type)

Compression type	1/2"BSPP
adapter 12 mm OD	33.5
adapter 1/2" OD	33.5
adapter 20 mm OD	36.5
adapter 3/8" OD	30.7

Face-seal	1/2"BSPP
adapter 1/2" inlet	27.6

Compression type



*) Dimension A is typical finger-tight.

> Options and accessories

- Free software support for operation, monitoring, optimizing or to interface between digital instruments and windows software.



- BRIGHT compact local Readout/Control module
- E-5700 / E-7000 Power Supply



- Interconnecting cables for power and analog/digital communication
- PiPS Plug-in Power Supply



- Optional ATEX Zone 2 Cat. 3 protection. Hereto we will furnish extra cover(s) for mechanical impact protection (see pictures), including applicable certificate(s).



> Alternatives

- IN-FLOW^{CTA} direct (no by-pass) Mass Flow Meter model T12 (flow capacities from 5 up to 50 l_n/min Air-equivalent Full Scale)
- IN-FLOW^{CTA} direct (no by-pass) Mass Flow Meter model T14 (flow capacities from 100 up to 1000 l_n/min Air-equivalent FS)



- LOW-ΔP-FLOW series (by-pass style) Mass Flow Meter for low pressure drop applications or corrosive gas service



По вопросам продаж и поддержки обращайтесь:

Волгоград +7 (8442) 45-94-42
Екатеринбург +7 (343) 302-14-75
Ижевск +7 (3412) 20-90-75
Казань +7 (843) 207-19-05

Краснодар +7 (861) 238-86-59
Красноярск +7 (391) 989-82-67
Москва +7 (499) 404-24-72
Ниж.Новгород +7 (831) 200-34-65

Новосибирск +7 (383) 235-95-48
Омск +7 (381) 299-16-70
Пермь +7 (342) 233-81-65
Ростов-на-Дону +7 (863) 309-14-65

Самара +7 (846) 219-28-25
Санкт-Петербург +7 (812) 660-57-09
Саратов +7 (845) 239-86-35
Сочи +7 (862) 279-22-65

сайт: bronkhorst.pro-solution.ru | эл. почта: brk@pro-solution.ru
телефон: 8 800 511 88 70